

TREE PLANTING DETAIL  
Scale 1:20

No.	Species	Specification	Spacing
4	Acer campestre 'Red Shine'	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown
6	Alnus incana	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown
7	Betula pubescens	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown
3	Fagus sylvatica Dawyc Gold'	Feathered, 3x 10-12cm, 3-3.5cm ht, rootballed, well balanced crown, min. 7 branches.	as shown
4	Prunus padus	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown
2	Sorbus aria 'Majestica'	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown
1	Sorbus aucuparia 'Cardinal Royal'	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown
3	Tilia cordata 'Rancho'	Standard (Heavy) 3x 12-14cm, 3.5-4.25cm ht 1.75-2m clear stem, rootballed, well balanced crown, min. 5 branches.	as shown

ESTABLISHMENT & MAINTENANCE SCHEDULE	Year																																
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	
Site and shrub establishment inspection																																	
Pruning and thinning (outside the leaf nesting season)																																	
Dead tree removal																																	
Fertiliser application																																	
Standard herbicide application																																	
Specialised herbicide application																																	
Check stakes, ties and tree jackets (removal after 3 years)																																	
Check & take leaf removal																																	
Inspection and wire tightening																																	

**SPECIFICATION NOTES**

**Tree Pits**  
Heavy standard trees to be planted into prepared pits 900 x 900 x 600mm deep. Any compacted material at the base of the pit to be forked a further 200mm to provide demonstrable drainage. Backfill to consist of a 150mm layer of straight stone and topsoil excavated from the pit with 25% Treestart Peat-Free planting compost and incorporated with 500g of Broadleaf P4 granules. Sierrabl Flora Tablets slow release fertiliser incorporated into the tree pit at a rate of 10 tablets per tree, placed at the side of the root zone halfway up the backfill, no deeper than 20cm and distributed evenly around the rootball.


**Staking**  
65mm dia stake 3250mm long driven as shown, 2no. rubber tree ties and spacers securely nailed to stake. All stakes to be once weathered and given 2 coats of dark brown woodstain.

**Watering and Mulch**  
Install watering pipe as shown and water in trees after planting. 500mm radius area around each tree to have 50mm depth of medium grade bark spread.

**Turf**  
Disturbed ground shall be prepared to receive Rowlaw Medallion or similar approved turf to reinstaate.

**Root Containment**  
Services within 2000mm of trees to be protected by the installation of REROOT 600 ribbed root deflection barrier by Greenleaf Products or similar approved. Precised position to be agreed on site. All joints to be made good with jointing tape to ensure they are root proof.

REVISIONS	
NO.	DATE
** ***	** ** *
** ***	** ** *



SCALE 1:200  
0 2 4 10m



**Connon Design**  
Landscape Architects  
Unit 1.1, 59 Main Street,  
Cumbemauld, G67 2RT  
Tel: 01236 780660  
Email: info@connondesign.co.uk  
www.connondesign.co.uk

CLIENT:  
SCOTTISH WATER

PROJECT:  
P005, GARRIOCHMILL ROAD CSO

STATUS:  
**PLANNING**

DRAWING TITLE:  
PLANTING PLAN

DRAWING NUMBER:  
5336.002

NORTH  
↑

REVISION:	SCALE:	SHEET:
-	1:200@A1	A1
DATE:	DRAWN:	CHECKED:
05.02.19	BC	NT